

Pengaruh percepatan waktu pelaksanaan terhadap biaya pada pekerjaan struktur bawah jembatan di Kabupaten Buatan Pekanbaru Riau = The influence of implementation time acceleration toward the cost on the highway bridge s sub structure at Buatan Pekanbaru Riau

Isma Kania Muthmainah Sutisna, author

Deskripsi Lengkap: <https://lib.ui.ac.id/detail?id=20348115&lokasi=lokal>

Abstrak

Pembangunan proyek Jembatan, di Kabupaten Buatan, Pekanbaru, Riau bertujuan untuk mendukung pendistribusian produksi PT. Pertamina Riau. Namun, pada kenyataannya, lokasi proyek yang kurang memadai menjadi kendala dalam pengiriman alat-alat berat serta pengadaan peralatan kerja yang membuat waktu pekerjaan semakin lama. Oleh karena itu, untuk mencapai tujuan proyek dari segi waktu maka dilakukan percepatan waktu pelaksanaan dengan menggunakan metode cost slope dan Time Cost Trade Off (TCTO) yang diharapkan proyek jembatan ini dapat selesai lebih cepat dengan memperhitungkan biaya yang paling efektif. Alternatif percepatan waktu yang dilakukan adalah dengan menambah jam kerja (lembur) dan jumlah pekerja. Berdasarkan hasil perhitungan dua alternatif maka dipilihlah alternatif penambahan jam kerja (lembur) dengan percepatan waktu yang paling optimal dan pengurangan durasi proyek sebesar 8 hari dari biaya total Rp2.505.912.167,19.

.....Highway Bridge's construction project at Buatan, Pekanbaru, Riau aims to support distribution of production from PT. Pertamina Pekanbaru, Riau. Whereas,in fact, the site of project inadequate become an obstacle on deliver and provide heavy equipments so that spending activities much longer. Therefore, to achieve the project goals must accelerate execution of time with cost slope and Time Cost Trade Off (TCTO) method, then hopefully, Highway bridge's project could achieve faster by taking account of the cost effective. To apply time acceleration alternative by adding time of work (overtime) and number of employees. According to two alternatives of calculation, so that the best option has been selected the time of work (overtime) which had optimal time acceleration and reduced project duration 8 days of the total cost project is Rp2,505,912,167.19.