

Pengembangan Standar Perencanaan Biaya Pekerjaan Design Development, Sitework, dan Struktur pada Pekerjaan Kawasan Stadion pada Kontrak Terintegrasi Rancang Bangun Gedung Negara Berbasis Permen PU No 22 Tahun 2018 untuk Meningkatkan Akurasi Biaya = Development of Cost Planning Standard for Design Development, Sitework, Structure on Stadion Area Works in Integrated Contracts of State Building Design Based on Indonesian Minister of Public Works Regulation No 22 Of 2018 to Improve Cost Accuracy

Sebayang, Gabriel Pratama, author

Deskripsi Lengkap: <https://lib.ui.ac.id/detail?id=20525808&lokasi=lokal>

Abstrak

Pembangunan Stadion sangatlah kompleks karena kerumitan dan kompleksitasnya maka metode kontrak terintegrasi rancang bangun dinilai lebih efisien untuk diterapkan dibandingkan metode konvensional. Namun, masih ada masalah atau penyebab kegagalan untuk melaksanakan kontrak desain. Salah satu contoh masalah fantastis yang muncul pasca pembangunan Proyek Asian Games XVIII 2018 adalah adanya sengketa cost mismatch dimana total kerugian akibat sengketa ini sebesar Rp. 5,3 triliun dari Rp. 7,4 triliun anggaran. Dalam proyek pembangunan The Montreal Olympic Stadium dimana Stadium Area telah mengalami pembengkakan biaya sebesar \$60 juta. Proyek ini mengalami kerugian sebesar \$270 juta karena ada masalah pada tahap pengembangan desain dan karena itu pekerjaan lokasi karena tidak ada ruang untuk slip jadwal. Insiden lain yang berkaitan dengan struktur adalah menimpa Miller Park pada tahun 2001, diperlukan \$ 13 juta untuk perbaikan yang dibayarkan karena kerusakan. Melihat delik masalah yang terjadi. Maka Penelitian ini bertujuan untuk mengembangkan standar perencanaan biaya untuk design development, sitework, dan struktur pada pekerjaan area stadion pada kontrak terintegrasi rancang bangun gedung negara berdasarkan Keputusan Menteri PUPR No 22 tahun 2018 untuk meningkatkan akurasi biaya. Penelitian ini diawali dengan studi pustaka untuk menetapkan dan mengidentifikasi latar belakang masalah dan sebagai penunjang penelitian, selanjutnya dilakukan perumusan dalam pertanyaan penelitian yaitu biaya standar dan non standar, standar spesifikasi teknis, standar penyajian biaya, standar biaya per meter persegi, dan standar biaya per kursi untuk mendapatkan hasil yang dapat dipertanggungjawabkan secara akademis, penelitian ini akan menggunakan metode validasi dan uji statistik seperti Metode SEM dan SPSS. Hasil penelitian ini diharapkan dengan adanya Standar Perencanaan Biaya dapat meningkatkan akurasi biaya dan tidak mengalami pembengkakan biaya dalam pelaksanaan proyek yang menimbulkan kerugian besar seperti sebelumnya. Temuan model matematis hasil penelitian ini adalah berdasarkan Original Sample (O) yaitu $Y = 0.573X_1 - 0.249X_2 + 0.229X_3$. Dapat juga dikatakan bahwa tingkat akurasi meningkat jika variabel X_1 Standard Cost dan X_3 Miscellaneous Expenses dinaikkan, dan tingkat akurasi juga meningkat jika variabel X_2 dinaikkan. Biaya Non-Standar berkurang. Dapat dilihat bahwa model yang dihasilkan dapat mewakili kondisi sebenarnya di lapangan sebesar 64,3%.

.....The stadium is very complex because of the complexity the design and build integrated contract method is considered efficient to apply than the conventional method. However, there are still problems or causes of failure to implement the design contract. One example of a fantastic problem that arise after the construction of the 2018 Asian Games XVIII Project was that there was a dispute regarding a cost mismatch where The

total loss caused by this dispute amounted to Rp. 5.3 trillion from Rp. 7.4 trillion of the budget. In the construction project of The Montreal Olympic Stadium where the Stadium Area has experienced a cost swelling of \$ 60 million. This project suffered a loss of \$270 million because there is a problem at the design development stage and Because of that the sitework as there was no room for schedule slippage. Other incidents related to the structure is the befell Miller Park in 2001, required \$13 million in repairs paid because of the malfunction. Seeing the offense of the problem. This research aims to develop the cost planning standards for design development, sitework, and structure on stadium area works on integrated contracts based on state building design based on PUPR Ministerial Decree No 22 year of 2018 to improve cost accuracy. This research began with a literature study to establish and identify the background of the problem and as a support for the study, then the formulation is carried out in research questions there are standard and non-standard cost, technical specification standards, cost presentation standards, cost standards per square meter, and cost standards per seat to get results that are academically justifiable, this research will use validation methods and statistical tests like SEM and SPSS Method. The results of this research were expected with the existence of a Cost Planning Standard can increased cost accuracy and not experiencing cost overruns in project implementation which caused large losses as before. for the mathematical model of the research results based on the Original Sample (O), namely $Y = 0.573X_1 - 0.249X_2 + 0.229X_3$. It can also be said that the level of accuracy increases if the variable X_1 Standard Cost and X_3 Miscellaneous Expenses is increased, and the accuracy rate is also increased if the X_2 variable is increased. Non-Standard Costs are reduced. it can be seen that the resulting model can represent the actual conditions in the field by 64.3%.